No.	Name of work	Unit	Quantity
	CONSTRUCTING TUNNELS AT JUNCTIONS OF ROAD.		
10	Earthwork excavating the foundation	C.yd.	48
11	New size stone in surki mortar	C.ft.	1,296
12	Cement pointing to stone masonry	Sqr.	18.64
13	Providing and fixing new burnt stone slabs 6" thick roughly dressed over the masonry for covering, including forming earthwork over it, etc., complete	S.ft.	864

K. S. HUTCHA RAO,
Sanitary Engineer.

KOLAR DIVISION.

Abstract Notification dated 28th May 1940.

The attention of the public is invited to the detailed Notification, dated 26th May 1940, published on pages 1295-1297, Part VI of the *Mysore Gazette*, dated 6th June 1940, *re* tenders for constructing a Masonry Dam and Head Sluice with earthen flank bund across the halla at the junction of the Weir Halla of Doddakurugode Tank and other small hallas and opening out a Feeder Channel from the Dam to the Kudumalakunte Malleswarakere, Register No. 18, in Goribidnur Taluk.

The last date for lodging of tender is 21st June 1940, up to 2 P.M.

Abstract Notification dated 28th May 1940.

The attention of the public is invited to the detailed Notification, dated 26th May 1940, published on pages 1298-1299, Part VI of the *Mysore Gazette*, dated 6th June 1940, regarding tenders for constructing a car shed for the car of Sree Ramalingeswara Temple at Avani, Mulbagal Taluk. The last date for lodging of tender is up to 2 P.M. on 21st June 1940.

Notification dated 8th June 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 29th June 1940, for maintenance work to Kandavara Amanikere (Major) R. No. 6 in Chikballapur Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for maintenance work of Kandavara Amanikere (Major) R.No. 6 in Chikballapur Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury chellan for earnest money of Rs. 130, paid to the treasury to the credit of "17 (*a*) P. W. Deposits," against the account of the Executive Engineer, Kolar Division, Kolar. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 29th June 1940 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form for the due fulfilment of the contract and for the execution of all items of work in accordance with the Bombay Specifications. A reserve of 5 per cent will be withheld in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings, may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. When lumpsum provisions are shown in the schedule of quantities, the contractor will be paid at either his tendered rate for each item or the prevailing schedule of rates in the division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reason whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of February 1941, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21 All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D. so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N.B.—Copies of tenders in the prescribed form are obtainable from the Office of the Executive Engineer, Kolar Division, Kolar, only on a payment of four annas per form.

Abstract estimate for maintenance work of Kandavara Amanikere (Major) Reg. No. 6 in Chickballapur Taluk.

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
			Rs. a. p.		Rs. a. p.
1	Cutting and removing jungle (thin Lantana) with roots	Grade L. S.	0 8 0 ..	50 ..	
2	Removing ant-hills and filling with good sand ..				
3	Cutting longitudinal steps and grips in front and rear slopes and at top	Grade	2 0 0	50	
4	Earthwork to bund with watering and consolidation including lead and a lift of 25 ft.	C.yd.	0 3 6	6,080	
5	Turfing slopes including watering, etc., complete ..	S.yd.	0 0 9	18,230	
6	Gravelling the top of bund with extra average lead of $\frac{7}{8}$ mile	C.yd.	0 10 0	264	
	Total ..				

Notification dated 8th June 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 29th June 1940, for restoring Chadumanahalli Kodagikere tank, Reg. No. 43 (unrestored Minor) in Kolar Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for restoring Chadumanahalli Kodagikere tank, Reg. No. 43 (unrestored Minor) in Kolar Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a Treasury chellan for earnest money of Rs. 250 paid to the Treasury to the credit of "17(a) P. W. deposits" against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 29th June 1940 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract and for the execution of all items of work in accordance with the Bombay specifications. A reserve of five per cent will be withheld in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. When lumpsum provisions are shown in the schedule of quantities the contractor will be paid at either his tendered rate for each item or the prevailing schedule of rates in the division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of April 1941, failing which, the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parabs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents, and if necessary, provide for the same by insurance at the proper time.

Note.—(b) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N.B.—Copies of tenders in the prescribed form are obtainable from the office of the Executive Engineer, Kolar Division, Kolar, only on a payment of Re. 0-4-0 per form.

Abstract estimate for restoring Chadumanahalli Kodagikere, Reg. No. 43—796 of Kolar Taluk (unrestored Minor).

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
	Bund at R. L. 57.00.		Rs. a. p.		Rs. a. p.
1	Clearing jungle with roots	Grade	2 0 0	12	
2	Earthwork excavation, cutting grips and trenches for the seat of new earthwork	,,	2 0 0	18	
3	Removing ant-hills and filling with sand	L. S.			
4	Earthwork to bund with lead and lift including watering and consolidation, etc. complete	C.yd.	0 2 9	9,214	
5	Turfing the slopes of bund	S.yd.	0 0 9	5,317	
6	Removing and resetting the old revetment wherever necessary with jelly wedging after removing roots	L. S.			
7	Constructing new rough stone revetment with jelly wedging	C.yd.	1 8 0	784	
8	Constructing good clay puddle core wall well kneaded and consolidated	,,	0 8 0	64	
9	Providing and fixing new grade stones with figuring and painting	Each	1 8 0	20	
10	Do Index stones with bed stones	,,	0 6 0	20	
11	Removing, painting and fixing B. M. stones	,,	1 0 0	2	
12	Providing and fixing Reg. No. stone with figuring and painting	,,	3 0 0	1	
	Total				
	Constructing a new Cast Iron pipe sluice at C. S. No. 10 with Cill at 43.00.				
1	Earthwork excavation for foundation	C.yd.	0 2 6	3	
1	Burnt stone jelly concrete in surki mortar	C.ft.	0 4 0	84	
3	Size stone in surki mortar with necessary bond stones	,,	0 4 6	177	
4	Burnt stone slabs 6" thick dressed and fixed in surki mortar	S.ft.	0 4 6	49	
5	Cement mortar pointing after raking joints (pro. 1 : 3)	Sqr.	3 8 0	2.70	
6	Providing cast iron pipes of 6" diar. including carting, Railway freight and hoisting fixing, etc., complete	R.ft.	3 0 0	48	
7	Providing a new plug and rod with locking arrangement	Each	15 0 0	1	
8	Dismantling the existing damaged sluice	L. S.			
9	Drilling holes in orifice slabs	Each	1 0 0	2	
	Total				
	Constructing a masonry waste weir at R. L. 52.00, 55 feet long.				
1	Earthwork excavation for foundation	C.yd.	0 2 6	32	
2	Burnt stone jelly concrete in surki mortar	C.ft.	0 4 0	304	
3	Burnt size stone in surki mortar	,,	0 4 6	832	
4	Burnt stone slabs 6" thick dressed and fixed in surki mortar	S.ft.	0 4 6	156	
5	Cement mortar pointing after raking joints (1 : 3)	Sqr.	3 8 0	9.50	
6	New rough stone work with jelly wedging	C.yd.	1 8 0	89	
7	Providing joggle joints	Each	0 8 0	8	
	Total				

C. R. IYENGAR,
Executive Engineer.

61